


BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Construction of Temporey Immersion Tank for Lord Ganesha idols at Rachenahalli Lake Near Muneshwara Temple in Ward NO 06, Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	31.5	Earth work in surface excavation in Hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	173.84	One hundred Seventy Three point Eight Four only
2	185.25	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m. In depth with lead upto 50m. after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	223.66	Two hundred and Twenty Three point Six Six only
3	185.25	Above 1.5 Mtrs Depth Add 25% Extra	Cum	279.58	Two hundred & Seventy nine point Five Eight
4	1000	Providing Plastic Sheet etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	6	Six
5	187	Supply of water Through water Tank for filling Tank etc., complete and as per the directions of the Engineer-in-charge of the work	Each	350	Three hundred & fifty only
6	30	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to slipping Sl No. 50 P II Code 400 metal Component etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	200	Two hundred only
7	88	Hire charge of pumping water 3.5 KL/hr capacity Pump etc., complete and as per the directions of the Engineer-in-charge of the work	Hr	35	Thirty five only
8	132	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc., complete and as per the directions of the Engineer-in-charge of the work	Days	192.4	One hundred & Ninety Two point Four only
9	3410	Hire Charges for Two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 0.50 mtrs C/C Horizontaly with Necessary earth work and labour etc., complete and as per the directions of the Engineer-in-charge of the work	Rft	17	Seventeen only


Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc., complete and as per the directions of the Engineer-in-charge of the work	Sft	3	Three only
11	550	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc., complete and as per the directions of the Engineer-in-charge of the work	Rft	17	Seventeen only
12	660	Hire Charge for Armless Plastic Chairs etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	4	Four only
13	132	Hire Charge for Wooden Table of Size 6ft x 2ft etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	40	Forty only
14	3080	Hire Charge for supplying and running circuit service main with necessary messenger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathed aluminium wire etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	9	Nine only
15	110	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc., complete and as per the directions of the Engineer-in-charge of the work	Hr	495	Four hundred & Ninety five only
16	154	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	285	Two hundred & Eighty five only
17	10	Hire charges compoment name 1087 Crane charges etc., complete and as per the directions of the Engineer-in-charge of the work	Day	3200	Three Thousand Two hundred only
18	370.5	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	60.48	sixty four point eight only


B. Vengopal Reddy

Signature of the Contractor



Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಬೆಂಡರ್ ಪಡ್ಕೂರ್ನ್ನು
ಕಿದ್ದುಪಡೆಗಲ ಸಂಖ್ಯೆ.....
ಕಿದ್ದುಪಡೆ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರಾಗಿದೆ



Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

29/10/2014